

PEPPER LUCE CREEK CULVERT REPLACEMENT AT SHAKER BOULEVARD

Pepper Pike, OH

CHAGRIN RIVER · PEPPER LUCE CREEK

Summary

The project included replacement of approximately 350 feet of a failing 48-inch corrugated metal culvert downstream from Shaker Boulevard in Pepper Pike and attempt to reduce local flood risk. The culvert exhibits segments where the bottom has rusted away. Debris is being trapped by the up-curved and rotted out pipe bottom in some upstream segments. Basement flooding of a number of homes reported on May 28, 2017 and August 10, 2017 as well as temporary closure of Shaker Blvd.

Project Details

Asset ID(s): PC00113

Contract Type: Partner Project

Construction Cost: \$750,000.00

Completed Date: March 31, 2020

Watershed Team Leader: Francisco Rivera (riveraf@neorsd.org)



REGIONAL
STORMWATER
MANAGEMENT